

ਮਤਾ ਨੰਬਰ: - 25

ਵਿਸ਼ਾ:- ਵਿਕਾਸ ਦੇ ਕੰਮਾਂ ਦੇ ਟੈਂਡਰਾਂ ਦੀ ਪ੍ਰਵਾਨਗੀ ਸਬੰਧੀ ।

ਹੇਠ ਲਿਖੇ ਵਿਕਾਸ ਦੇ ਕੰਮਾਂ ਦੇ ਟੈਂਡਰ ਬੀ.ਐਂਡ ਆਰ. ਸ਼ਾਖਾ ਵਲੋਂ ਮੰਗੇ ਗਏ । ਮਾਨਯੋਗ ਕਮਿਸ਼ਨਰ ਜੀ ਦੇ ਹੁਕਮ ਮਿਤੀ 3123 ਮਿਤੀ 16.3.2023 ਅਨੁਸਾਰ ਨੈਗਸਿਏਸ਼ਨ ਕਰਨ ਉਪਰੰਤ ਕੰਮਾਂ ਦਾ ਵੇਰਵਾ ਹੇਠ ਲਿਖੇ ਅਨੁਸਾਰ ਹੈ:

Sr. No.	Name of Work	House Reso.	Est.Amt . (In Lacs)	Correct/ vetted BOQ amt.(In Lacs)	No. Tenders received	Name of Agency	Tender Received	Saving % age	Saving After Negotiation	Tender Amt.
Central Constituency										
1.	P/L of Cement Conc. In the street of Karar Khan Mohalla and Gopal Nagar	64(25) 07.01.2023	6.28	6.27	2	The Laxmi Co.op L/C Society	1 st time	-2.07%	-5.00%	5.96
2.	P F of I/Tiles in the streets of kot ram dass	65(01) 07.01.2023	10.06	9.70	2	The Kundal Co-op L/c society	2nd time	-32.15%	-32.15%	6.58
3.	P/L of RMC M30 on the streets of civil line area around Patel hospital.	65(10) 07.01.2023	46.46	45.80	2	The Inderprast Co-op L/c Society	1 st time	-2.50%	-5.00%	43.51
4.	P L of RMC in the streets of Mohyal Nagar	63(06) 07.01.2023	28.50	28.22	2	The Laxmi Co-op L/c Society	1 st time	-2.07%	-5.00%	26.81
5.	P/L of RMC M-30 in Area near Hanuman Mandir W.No.52	65(19) 07.01.2023	22.03	21.62	2	The Suraj Co.op L/C Society	1 st time	-1.00%	-2.00%	21.19
6.	P/L of RMC M-30 on the streets opposite Dolphin hotel, old Sabji Mandi W.no.52	65(18) 07.01.2023	16.77	16.73	2	The Suraj Co.op L/C Society	1 st time	-1.00%	-2.00%	16.40
7.	Repair and Renovation of Bohar wala park Shakti Nagar W.No.49	63(08) 07.01.2023	26.18	25.55	2	The Satnam Co.op L/C Society	1 st time	-2.08%	-4.00%	24.53
8.	Repair and Renovation of Shakti Nagar Market wala park, Shakti Nagar W.No.49	63(05) 07.01.2023	32.19	32.19	2	The Satnam Co.op L/C Society	1 st time	-2.11%	-4.00%	30.90
9.	Const. of park near Lal Rattan Zone in W.No.49	63(06) 07.01.2023	12.53	11.90	2	The Kundal Co.op L/C Society	1 st time	-1.00%	-3.00%	11.54
10.	P/L of RMC in the streets of Ravidass park near National Avenue	65(05) 07.01.2023	36.80	36.67	2	The New Amare Co.op L/C Society	1 st time	-2.03%	-5.00%	34.84
11.	P/L of SDBC in Internal Streets bof Guru Gobind Singh Avenue Adjoining Flat sides	65(03) 07.01.2023	28.48	26.89	2	Satish Aggarwal and Co.	1 st time	-10.88%	-10.88%	23.96

12.	P/L WBM and BM & PC in revenue road Ladhewali and Basant Hill W.No.8	65(02) 07.01.2023	45.90	43.57	2	Satish Aggarwal and Co.	1 st time	-10.88%	-10.88%	38.83
13.	P/L of BM & PC on main road from Football Chowk to Jhandian Wala Peer chowk W.No.48	65(23) 07.01.2023	49.72	46.66	4	Satish Aggarwal and Co.	1 st time	-10.88%	-10.88%	41.58
14.	P/L of SDBC on the road of Vijay Nagar W.no.49	65(10) 07.01.2023	20.68	19.23	3	Satish Aggarwal and Co.	1 st time	-10.88%	-10.88%	17.14
15.	P/L BM & PC on the road Backside Fire Bridge Office Baaje Bazaar W.no.52	65(17) 07.01.2023	30.83	29.23	3	Satish Aggarwal and Co.	1 st time	-10.88%	-10.88%	26.05
16.	P/L of BM and PC on road from Skylark to Rangla Vehra W.No.50	65(12) 07.01.2023	44.88	43.01	3	Satish Aggarwal and Co.	1 st time	-10.88%	-10.88%	38.33
17.	P/L of BM & SDBC in Jawahar Nagar market near Heat-7 W.No.20	65(13) 07.01.2023	15.36	15.14	3	Satish Aggarwal and Co.	1 st time	-10.88%	-10.88%	13.49
18.	P/F of Interlocking Tiles on revenue road in Punjab Avenue	65(04) 07.01.2023	7.56	7.53	3	The Rarah Co.Op L/c society	1 st time	-12.88%	-12.88%	6.56
19.	P F of tiles in revenue road in village Dhilwan	65(07) 07.01.2023	12.55	12.07	3	The Rarah Co.Op L/c society	1 st time	-19.28%	-19.28%	9.74
20.	P/F of Interlocking Tiles in Revenue Road Back side G.N.D.U University	65(09) 07.01.2023	29.02	27.01	3	The Rarah Co.Op L/c society	1 st time	-19.27%	-19.27%	21.81
21.	P/L of interlocking Tiles at Guru Gobind Singh Avenue	65(11) 07.01.2023	35.67	35.49	4	The Doaba Co.Op L/c society	1 st time	-20.21%	-20.21%	28.32
22.	P/L of Interlocking Tiles and footpath near Lajpat Nagar market W.No.20	65(16) 07.01.2023	7.11	7.03	2	the kotli jattan co op l and c society	1 st time	-2.02%	-5.00%	6.68
23.	P/L of RMC M-30 in Badridass Colony	65(24) 07.01.2023	8.63	8.49	3	The Rarah Co.Op L/c society	1 st time	-8.88%	-8.88%	7.74
24.	P/L of Interlocking Tiles in Revenue Road birring	65(26) 07.01.2023	48.24	48.24	2	The Sham Chaurasi Co.Op L/c society	1 st time	-13.99%	-13.99%	41.49
West Constituency										
25.	Repair and maintenance of Freedom Fighter Mahant Agya Singh Park, 120 feet road	63(07) 07.01.2023	3.42	3.36	2	The Tej Mohan Co.Op L/C Society	1 st time	-1.23%	-2.23%	3.29
26.	Const. of CC streets in Kabir Vihar near Mandir	63(09) 07.01.2023	24.81	24.72	2	The Suraj Co.op L/C Society	1 st time	-1.68%	-5.00%	23.48

27.	Const. of CC streets Gali No. 4 and various streets in Shaheed Babu Labh Singh Nagar	63(11) 07.01.2023	35.18	35.01	2	The Ucha CO.op L/C society	1 st time	-2.40%	-5.00%	33.26
28.	P/L BM and PC in Chuna Bhathi road	63(12) 07.01.2023	32.86	31.03	4	Satish Aggarwal And Co.	1 st time	-12.88%	-12.88%	27.03
29.	P/L of BM and PC in Rameshwar Colony	63(13) 07.01.2023	36.57	34.38	3	Satish Aggarwal And Co.	1 st time	-12.88%	-12.88%	29.95
30.	P/L of PC in Shri Guru Ravidass Nagar and adj. area	63(14) 07.01.2023	42.90	40.28	2	Satish Aggarwal And Co.	1 st time	-13.88%	-13.88%	34.69
31.	P/L of 80mm thick interlocking tiles in main road in Kot Mohalla	63(15) 07.01.2023	26.71	26.15	2	The Dr. Ambedkar Co.Op L/C Society	1 st time	-1.98%	-5.00%	24.84
32.	Const. of CC streets in Kabir Vihar near Chuna Bhathi road.	63(16) 07.01.2023	17.63	17.56	2	The Karari Co.op L/C Society	1 st time	-1.45%	-5.00%	16.68
33.	P/L of BM &PC in Bank Colony road.	67(02) 07.01.2023	14.81	13.95	2	Satish Aggarwal And Co.	1 st time	-12.88%	-12.88%	12.15
34.	P/L of BM &PC in Model House.	67(03) 07.01.2023	35.24	33.23	4	Satish Aggarwal And Co.	1 st time	-12.88%	-12.88%	28.95
35.	Decoration and maintenance of Shri Bhagat Kabir Chowk	67(12) 07.01.2023	37.07	36.97	2	Neelkanth Contractors	1 st time	-0.11%	-1.50%	36.42
36.	Const. of various CC streets in Gobind Nagar	81(03) 07.01.2023	66.69	66.50	5	Gagan Deep Arora Govt. Contractor	1 st time	-31.96%	-31.96%	45.25
37.	P/L of BM & BC near Dashera Ground of Kala Singha road.	67(06) 07.01.2023	78.58	74.91	2	Ms. bhushan chhura and co	1 st time	-15.90%	-15.90%	63.00
38.	Const. of cc streets in Kabir Vihar near Beriyan wala School.	67(08) 07.01.2023	93.00	92.66	6	Gagan Deep Arora Govt. Contractor	1 st time	-31.96%	-31.96%	63.05
39.	Const. of various CC streets near Post office in W.No. 45	81(02) 07.01.2023	53.76	52.31	4	The Moga Co-Operative L/C Society	1 st time	-28.29%	-28.29%	37.51
40.	P/L of BM and SDBC in Basti Guzan road	67(13) 07.01.2023	63.12	61.27	2	Ms. bhushan chhura and co	1 st time	-15.90%	-15.90%	51.53
41.	P/F of 60mm thick interlocking tile in Shamshan Ghat near Ghas Mandi.	67(04) 07.01.2023	21.49	21.21	3	The Doaba Co.Op L/c society	1 st time	-18.11%	-18.11%	17.37
42.	Const. of cc streets of Ram Shranam Colony.	67(07) 07.01.2023	12.38	12.36	3	The Rarah Co.Op L/c society	1 st time	-8.99%	-8.99%	11.25
43.	Decoration of Babrik chowk and Babu Jagjivan Ram chowk.	67(09) 07.01.2023	46.99	46.86	4	The Sham Chaurasi Co.Op L/c society	1 st time	-12.13%	-12.13%	41.18
44.	P/F of 80mm thick tile in	67(11) 07.01.2023	27.90	27.56	3	The Doaba Co.Op L/c	1 st time	-25%	-25%	20.67

	Waryana Dump					society				
North constituency										
45.	Construction of RCC road Adda Hoshiarpur chowk Railway crossing W.No.55	64(01) 07.01.2023	47.52	47.49	2	The Moga Co.op L/C Society	1 st time	-2.01%	-3.00%	46.07
46.	Construction of various CC streets in new Abadi Santokhpura	64(07) 07.01.2023	25.21	25.00	2	The Jagdambay Co.op L/C Society	1 st time	-1.85%	-5.00%	23.75
47.	Laying WBM and SDBC on main Kotla road Hardyal Nagar (near Walia Ice cream)	64(08) 07.01.2023	15.27	15.27	2	Satish Aggarwal and Co.	1 st time	-10.88%	-10.88%	13.61
48.	Construction of CC streets in Dhan Mohalla (backside car wali kothi) W.No.55	64(09) 07.01.2023	9.32	9.31	2	The Blue Moon Co.op L/C Society	1 st time	-2.03%	-5.00%	8.84
49.	Construction of varius streets in Gandhi Nagar W.No.58	64(11) 07.01.2023	13.78	13.67	2	Adhi Co.op L/C Society	1 st time	-2.00%	-4.00%	13.12
50.	CC flooring for covering Drain in Rasta Mohalla W.No.54	64(12) 07.01.2023	3.08	3.08	2	The Laxmi Co.op L/C Society	1 st time	-2.07%	-3.07%	2.99
51.	Construction of CC streets in Aman Nagar	64(13) 07.01.2023	9.30	9.30	2	The New Amar Co.op L/C Society	1 st time	-2.63%	-5.00%	8.84
52.	Construction of CC streets at Surya Vihar	64(17) 07.01.2023	21.40	21.40	2	The Shiva Co.op L/C Society	1 st time	-2.07%	-5.00%	20.33
53.	Construction of CC street at Sawan Nagar	64(18) 07.01.2023	6.26	6.23	2	The Shiva Co.op L/C Society	1 st time	-2.07%	-5.00%	5.92
54.	P/L of cement conc in the street of kabir nagar ward no - 69	64(27) 07.01.2023	9.41	9.40	2	The Shivam Co-op L/c Society	1 st time	-2.11%	-5.00%	8.93
55.	P/L of cement conc in the street of Gandhi camp and Guru dev nagar w no-65	64(26) 07.01.2023	16.60	16.58	2	The Basti Nau Co-op L/c Society	1 st time	-3.13%	-5.00%	15.75
56.	P/L of cement conc in the street of preet nagar gurdwara saab ward no-61	64(28) 07.01.2023	10.00	9.92	2	The Basti Nau Co-op L/c Society	1 st time	-3.13%	-5.00%	9.42
57.	Construction of cc road in Ram nagar ward no 70	64(24) 07.01.2023	16.94	16.85	2	The New Amar Co-op L/c Society	1 st time	-3.03%	-5.00%	16.01
58.	P/L of WBM, BM and SDBC on main road Ravidass school to Lamba Pind (Kali road W.No. Gen)	64(02) 07.01.2023	72.61	68.75	2	M/S Bhushan Chhura and Co.	1 st time	-15.90%	-15.90%	57.82
59.	Construction of RCC road Bhagat Singh Chowk to Partap Bagh main gate	64(05) 07.01.2023	66.98	65.85	3	M/S Jai Shankar	1 st time	-27.29%	-27.29%	47.88

60.	Const of Various Streets In Laxmi Pura (Puri Market) W.No 60	64(03) 07.01.2023	11.45	11.41	3	The Rarah Co.Op L/c society	1 st time	10.99-%	10.99-%	10.16
61.	Const of CC Streets in Baldev nagar W.No.57	64(04) 07.01.2023	22.01	22.01	3	The Rarah Co.Op L/c society	1 st time	-11.27%	-11.27%	19.53
62.	Const of Various CC Streets in Dhan Mohalla near Disposal W.No 55	64(06) 07.01.2023	7.85	7.61	3	The Rarah Co.Op L/c society	1 st time	-9.88%	-9.88%	6.86
63.	Const. Of CC Parking in front of Guru Amardas Nagar Market	64(16) 07.01.2023	4.96	4.92	3	The Doaba Co.Op L/c society	1 st time	-6.18%	-6.18%	4.62
Cantt. Constituency										
64.	P/L of WBM, BM & PC main road at Nangal Krar Khan	66(03) 07.01.2023	31.85	31.84	3	Satish aggarwal and co	1 st time	-9.88%	-9.88%	28.69
65.	Const. of various streets in Shaheed Babu Labh Singh Nagar	63(10) 07.01.2023	51.11	51.03	4	the kotli jattan co op l and c society	1 st time	-27.99%	-27.99%	36.75

ਟੈਂਡਰ ਪ੍ਰਵਾਨਗੀ ਹਿਤ ਪੇਸ਼ ਹਨ।

ਸਹੀ/-
ਸ੍ਰੀ ਬਲਜੀਤ ਸਿੰਘ, ਕਾਰਜਕਾਰੀ ਇੰਜੀਨੀਅਰ (ਓ.ਐਂਡ ਐਮ.)

ਸਹੀ/-
ਸ੍ਰੀ ਸੁਖਵਿੰਦਰ ਸਿੰਘ, ਕਾਰਜਕਾਰੀ ਇੰਜੀਨੀਅਰ (ਬੀ.ਐਂਡ ਆਰ)

ਸਹੀ/-
ਸ੍ਰੀ ਅਨੁਰਾਗ ਮਹਾਜਨ, ਨਿਗਰਾਨ ਇੰਜੀਨੀਅਰ (ਓ.ਐਂਡ ਐਮ.)

ਸਹੀ/-
ਸ੍ਰੀ ਪੰਕਜ ਕਪੂਰ, ਡਿਪਟੀ ਕੰਟਰੋਲਰ (ਵਿੱਤ ਅਤੇ ਲੇਖਾ)

ਸਹੀ/-
ਸ੍ਰੀ ਰਜਨੀਸ਼ ਡੋਗਰਾ (ਮੈਂਬਰ ਸਕੱਤਰ)
ਨਿਗਰਾਨ ਇੰਜੀਨੀਅਰ (ਬੀ.ਐਂਡ ਆਰ)

ਸਹੀ/-
ਸ੍ਰੀ ਰਾਹੁਲ ਧਵਨ
ਨਿਗਰਾਨ ਇੰਜੀਨੀਅਰ (ਬੀ.ਐਂਡ ਆਰ)

ਇਹਨਾਂ ਟੈਂਡਰਾਂ ਸਬੰਧੀ ਕਮਿਸ਼ਨਰ ਜੀ ਨੇ ਪ੍ਰਵਾਨਗੀ ਦਿੱਤੀ ਹੈ ਅਤੇ ਜਿਸ ਦੀ ਪ੍ਰਸ਼ਾਸਕੀ ਪ੍ਰਵਾਨਗੀ ਨਗਰ ਨਿਗਮ ਤੋਂ ਲੋੜੀਂਦੀ ਹੈ। ਇੱਥੇ ਇਹ ਵਰਨਣ ਯੋਗ ਹੈ ਕਿ ਸਥਾਨਕ ਸਰਕਾਰ ਵਿਭਾਗ, ਪੰਜਾਬ, ਚੰਡੀਗੜ੍ਹ ਦੇ ਨੋਟੀਫੀਕੇਸ਼ਨ ਨੰ: 02.01.2023-5LG1/68 ਮਿਤੀ 25-01-2023 ਰਾਹੀਂ ਨਗਰ ਨਿਗਮ ਹਾਊਸ ਦੀ ਮਿਆਦ ਮਿਤੀ 24.1.2023 ਨੂੰ ਖਤਮ ਹੋਣ ਉਪਰੰਤ ਪੰਜਾਬ ਮਿਊਂਸਪਲ ਕਾਰਪੋਰੇਸ਼ਨ ਐਕਟ-1976 ਦੀ ਧਾਰਾ 407-ਏ ਉਪ-ਧਾਰਾ-1 ਤਹਿਤ ਨਗਰ ਨਿਗਮ ਹਾਊਸ ਦੀਆਂ ਉਕਤ ਐਕਟ ਵਿੱਚ ਦਰਜ ਸਾਰੀਆਂ ਸ਼ਕਤੀਆਂ ਨੂੰ ਇਸਤੇਮਾਲ ਕਰਨ ਲਈ ਕਮਿਸ਼ਨਰ, ਨਗਰ ਨਿਗਮ ਨੂੰ ਬਤੌਰ ਐਡਮਿਨਿਸਟ੍ਰੇਟਰ ਨਿਯੁਕਤ ਕੀਤਾ ਹੈ। ਇਹਨਾਂ ਟੈਂਡਰਾਂ ਦੀ ਪ੍ਰਸ਼ਾਸਕੀ ਪ੍ਰਵਾਨਗੀ ਦੇਣ ਦੀ ਸਿਫਾਰਸ਼ ਕੀਤੀ ਹੈ।

ਉਕਤ ਟੈਂਡਰ ਮਾਨਯੋਗ ਐਡਮਿਨਿਸਟ੍ਰੇਟਰ ਜੀ ਦੀ ਪ੍ਰਵਾਨਗੀ ਹਿਤ ਪੇਸ਼ ਹੈ ਜੀ।

ਫੈਸਲਾ:

ਪ੍ਰਵਾਨ ਹੈ।

ਸਹੀ/- ਅਭੀਜੀਤ ਕਪਲਿਸ਼, ਆਈ.ਏ.ਐਸ.,
ਐਡਮਿਨਿਸਟ੍ਰੇਟਰ,
ਨਗਰ ਨਿਗਮ ਜਲੰਧਰ
24.3.2023

ਮਤਾ ਨੰਬਰ: - 26

ਵਿਸ਼ਾ:- ਵਿਕਾਸ ਦੇ ਕੰਮਾਂ ਦੇ ਟੈਂਡਰਾਂ ਦੀ ਪ੍ਰਵਾਨਗੀ ਸਬੰਧੀ।

ਉਪਰੋਕਤ ਵਿਸ਼ੇ ਅਧੀਨ ਵਿਕਾਸ ਦੇ ਕੰਮਾਂ ਦੇ ਟੈਂਡਰ ਓ.ਐਂਡ.ਐਮ ਸ਼ਾਖਾ ਵਲੋਂ ਮੰਗੇ ਗਏ।

ਮਾਨਯੋਗ ਕਮਿਸ਼ਨਰ ਜੀ ਦੇ ਦਫਤਰੀ ਹੁਕਮ ਨੰਬਰ 3123 ਮਿਤੀ 16-03-2023 ਅਨੁਸਾਰ ਨੈਗੋਸੀਏਸ਼ਨ ਕਰਨ

ਉਪਰੰਤ ਕੰਮਾਂ ਦਾ ਵੇਰਵਾ ਹੇਠ ਲਿਖੇ ਅਨੁਸਾਰ ਹੈ:-

Sr. No.	Name of Work	House Reso.	Est. Amt (In Lacs)	Correct/vett ed BOQ Amt. (In lacs)	No. Tender Receiv ed	Name of Agency	Tender Receiv ed	Saving % age	Saving after Negoti ation	Tender Amt.
1	Annual Estimate for Desilting of Sewer Line Manholes with Super Suction Machine in different areas of Ward falling in Zone No. 3	60 07-01-23	48.84	4620282.00	4	M/s Rai Const.	1 st Attem pt	5.40%	6%	4590960.00
2	Annual Estimate for Desilting of Sewer Line Manholes with Super Suction Machine in different areas of Ward falling in Zone No. 4		48.30	4569603.00	3	M/s Rai Const.		5.40%	6%	4540200.00
3	Annual Estimate for Desilting of Sewer Line Manholes with Super Suction Machine in different areas of Ward falling in Zone No. 5		45.10	4266645.00	3	M/s Rai Const.		5.40%	6%	4239400.00
4	Annual Estimate for Desilting of Sewer Line Manholes with Super Suction Machine in different areas of Ward falling in Zone No. 6		47.81	4522943.00	3	M/s Rai Const.		5.40%	6%	4494140.00
5	Annual Estimate for Desilting of Sewer Line Manholes under Zone No. 6 with Govt. Owned (Department) Suction machine for 24 inch dia & above Sewer Line		45.36	4291203.00	3	M/s Rai Const.		5.40%	6%	4263840.00
6	Annual Estimate for Desilting of Sewer Line Manholes with Super Suction Machine in different areas of Ward falling in Zone No. 5-A	60 07-01-23	45.47	3443265.00	2	Baba Deep Singh Builders & Desilters Pvt.	1 st Attem pt	2.25%	6%	4274180.00
7	Annual Estimate for Desilting of Sewer Line Manholes with Super Suction Machine in different areas of Ward falling in Zone No. 1	60 07-01-23	40.50	3443265.00	3	Malwa & Co.	1 st Attem pt	15%		
8	Annual Estimate for Desilting of Sewer Line Manholes with Super Suction Machine in different areas of Ward falling in Zone No. 2	60 07-01-23	48.28	4049662.00	3	Malwa & Co.	1 st Attem pt	16.13%		
9	Annual Estimate for Desilting of Sewer Line Manholes with Super Suction Machine in different areas of Ward falling in Zone No. 7	60 07-01-23	40.50	3356980.00	3	Malwa & Co.	1 st Attem pt	17.13%		

10	Annual contract for maintenance of water supply and sewer lines falling under wards 46,73,75	60(12) 07.01.23	15.00			The Guru Nanakpura Co-op L/c Society		2.01%	6%	1410000.00
11	Annual contract for maintenance of water supply and sewer lines falling under wards 68,69,72	60(13) 07.01.23	15.00			The Guru Nanakpura Co-op L/c Society		2.01%	6%	1410000.00
12	Annual contract for maintenance of water supply and sewer lines falling under wards 76,77,78	60(11) 07.01.23	15.00			The Guru Nanakpura Co-op L/c Society		2.01%	6%	1410000.00
13	Annual contract for maintenance of water supply and sewer lines falling under wards 20	60(9) 07.01.23	5.00			The Guru Nanakpura Co-op L/c Society		2.01%	6%	470000.00
14	Annual contract for maintenance of water supply and sewer lines falling under wards 32,33,34	60(18) 07.01.23	15.00			The Guru Nanakpura Co-op L/c Society		2.01%	6%	1410000.00
15	Annual contract for maintenance of water supply and sewer lines falling under wards 35,36,37	60(17) 07.01.23	15.00			The Guru Nanakpura Co-op L/c Society		2.01%	6%	1410000.00
16	Annual contract for maintenance of water supply and sewer lines falling under wards 38,39,40	60(16) 07.01.23	15.00			The Guru Nanakpura Co-op L/c Society		2.01%	6%	1410000.00
17	Annual contract for maintenance of water supply and sewer lines falling under wards 41,42,43	60(15) 07.01.23	15.00			The Guru Nanakpura Co-op L/c Society		2.01%	6%	1410000.00
18	Annual contract for maintenance of water supply and sewer lines falling under wards 44,45,74	60(14) 07.01.23	15.00			The Guru Nanakpura Co-op L/c Society		2.01%	6%	1410000.00
19	Annual contract for maintenance of water supply and sewer lines falling under wards 11,12,13	60(21) 07.01.23	15.00			The Guru Nanakpura Co-op L/c Society		2.01%	6%	1410000.00
20	Annual contract for maintenance of water supply and sewer lines falling under wards 21,22,23		15.00			The Guru Nanakpura Co-op L/c Society		2.01%	6%	1410000.00
21	Annual contract for maintenance of water supply and sewer lines falling under wards 24,25,26	60(26) 07.01.23	15.00			The Guru Nanakpura Co-op L/c Society		2.01%	6%	1410000.00
22	Annual contract for maintenance of water supply and sewer lines falling under wards 27,28,29		15.00			The Guru Nanakpura Co-op L/c Society		2.01%	6%	1410000.00

23	Annual contract for maintenance of water supply and sewer lines falling under wards 30,31		10.00			The Guru Nanakpura Co-op L/c Society	2.01%	6%	940000.00
----	---	--	-------	--	--	--------------------------------------	-------	----	-----------

ਟੈਂਡਰ ਪ੍ਰਵਾਨਗੀ ਹਿਤ ਪੇਸ਼ ਹਨ।

ਸਹੀ/-
ਸ਼੍ਰੀ ਬਲਜੀਤ ਸਿੰਘ, ਕਾਰਜਕਾਰੀ ਇੰਜੀਨੀਅਰ (ਓ.ਐਂਡ ਐਮ.)

ਸਹੀ/-
ਸ਼੍ਰੀ ਸੁਖਵਿੰਦਰ ਸਿੰਘ, ਕਾਰਜਕਾਰੀ ਇੰਜੀਨੀਅਰ (ਬੀ.ਐਂਡ ਆਰ)

ਸਹੀ/-
ਸ਼੍ਰੀ ਅਨੁਰਾਗ ਮਹਾਜਨ, ਨਿਗਰਾਨ ਇੰਜੀਨੀਅਰ (ਓ.ਐਂਡ ਐਮ.)

ਸਹੀ/-
ਸ਼੍ਰੀ ਪੰਕਜ ਕਪੂਰ, ਡਿਪਟੀ ਕੰਟਰੋਲਰ (ਵਿੱਤ ਅਤੇ ਲੇਖਾ)

ਸ਼੍ਰੀ ਰਜਨੀਸ਼ ਡੋਗਰਾ (ਮੈਂਬਰ ਸਕੱਤਰ)
ਨਿਗਰਾਨ ਇੰਜੀਨੀਅਰ (ਬੀ.ਐਂਡ ਆਰ)

ਸਹੀ/-
ਸ਼੍ਰੀ ਰਾਹੁਲ ਧਵਨ
ਨਿਗਰਾਨ ਇੰਜੀਨੀਅਰ (ਬੀ.ਐਂਡ ਆਰ)

ਇਹਨਾਂ ਟੈਂਡਰਾਂ ਸਬੰਧੀ ਕਮਿਸ਼ਨਰ ਜੀ ਨੇ ਪ੍ਰਵਾਨਗੀ ਦਿੱਤੀ ਹੈ ਅਤੇ ਜਿਸ ਦੀ ਪ੍ਰਸ਼ਾਸਕੀ ਪ੍ਰਵਾਨਗੀ ਨਗਰ ਨਿਗਮ ਤੋਂ ਲੋੜੀਂਦੀ ਹੈ। ਇੱਥੇ ਇਹ ਵਰਨਣ ਯੋਗ ਹੈ ਕਿ ਸਥਾਨਕ ਸਰਕਾਰ ਵਿਭਾਗ, ਪੰਜਾਬ, ਚੰਡੀਗੜ੍ਹ ਦੇ ਨੋਟੀਫੀਕੇਸ਼ਨ ਨੰ: 02.01.2023-5LG1/68 ਮਿਤੀ 25-01-2023 ਰਾਹੀਂ ਨਗਰ ਨਿਗਮ ਹਾਊਸ ਦੀ ਮਿਆਦ ਮਿਤੀ 24.1.2023 ਨੂੰ ਖਤਮ ਹੋਣ ਉਪਰੰਤ ਪੰਜਾਬ ਮਿਊਂਸਪਲ ਕਾਰਪੋਰੇਸ਼ਨ ਐਕਟ-1976 ਦੀ ਧਾਰਾ 407-ਏ ਉੱਪ-ਧਾਰਾ-1 ਤਹਿਤ ਨਗਰ ਨਿਗਮ ਹਾਊਸ ਦੀਆਂ ਉਕਤ ਐਕਟ ਵਿੱਚ ਦਰਜ ਸਾਰੀਆਂ ਸ਼ਕਤੀਆਂ ਨੂੰ ਇਸਤੇਮਾਲ ਕਰਨ ਲਈ ਕਮਿਸ਼ਨਰ, ਨਗਰ ਨਿਗਮ ਨੂੰ ਬਤੌਰ ਐਡਮਿਨਿਸਟ੍ਰੇਟਰ ਨਿਯੁਕਤ ਕੀਤਾ ਹੈ। ਇਹਨਾਂ ਟੈਂਡਰਾਂ ਦੀ ਪ੍ਰਸ਼ਾਸਕੀ ਪ੍ਰਵਾਨਗੀ ਦੇਣ ਦੀ ਸਿਫਾਰਸ਼ ਕੀਤੀ ਹੈ।

ਉਕਤ ਟੈਂਡਰ ਮਾਨਯੋਗ ਐਡਮਿਨਿਸਟ੍ਰੇਟਰ ਜੀ ਦੀ ਪ੍ਰਵਾਨਗੀ ਹਿਤ ਪੇਸ਼ ਹੈ ਜੀ।

ਫੈਸਲਾ:

ਪ੍ਰਵਾਨ ਹੈ।
ਸਹੀ/- ਅਭੀਜੀਤ ਕਪਲਿਸ਼, ਆਈ.ਏ.ਐਸ.,
ਐਡਮਿਨਿਸਟ੍ਰੇਟਰ,
ਨਗਰ ਨਿਗਮ ਜਲੰਧਰ
24.3.2023